

#### **ALIGNMENT STUDY - DRAFT**

The project is to add on-street bike lanes to River Road between Zorn Avenue and Indian Hills Trail. Three Alternatives were studied:

- 1. Widening to the Left (north)
- 2. Widening to the Right (south)
- 3. Symmetric Widening

The project also includes the extension of the multi-use path on the right from the Peace Memorial to Indian Hills Trail which connects to the path from Indian Hills Trail to the Caperton Swamp.

#### **Design Criteria**

- ➤ Bike Lane Width = 5 feet
- Clear Zone = 3 feet
- Signing and Marking per 2009 MUTCD

There is an adjoining Kentucky Transportation Cabinet (KYTC) project that improves River Road from Beargrass Creek through the Zorn Avenue intersection. This project ties to existing River Road 700 feet east of Zorn Avenue (approximately at Mockingbird Valley Road). The profile grade of this KYTC project raises the existing grade approximately 2 feet. The plan does not include on-street bike lanes; however, there can be adjustments in lane widths to accommodate bike lanes.

#### **Typical Section**

The attached exhibits show the three alternatives. River Road travel lanes will be reduced from the existing 11 feet to 10 feet. The alternatives that widen either entirely left or right will correct the crown to the center; all alignments include an overlay of the existing road.

#### **Comparison Matrix**

Appendix A shows a comparison of each alternative broken out by segment.


#### **Photo Log**


Appendix B is a Photo Log broken out by segment.

#### **Utility Impacts**


The gas line is on the north (left) side of River Road. The water line and utility pole line is on the south (right) side. The gas line is not impacted by all alternatives. Widening to the south (right) and symmetric widening impact the water line and or the pole line.

#### EXIBIT 1 - TYPICAL SECTIONS





SYMETRICAL WIDENING



WIDENING RIGHT SIDE

#### Tree Preservation

After a review of all the trees with diameters greater than 10 inches, it was determined that the alternative selection should primarily be determined by factors and conditions other than existing trees. Nearly 75% of the trees are in Fair or Poor condition, meaning in no construction work were to occur, their service lives are limited to 10 years or less. Over30% are in Poor or Dead condition, and should be removed for public safety reasons regardless of any construction project activities. White ash trees comprise over 20% of the trees in the project area, and with Emerald Ash Borer confirmed in Jefferson County, they unfortunately can be considered expendable.

There are trees in Good condition that are providing valuable canopy cover and environmental benefits to River Road and the City as a whole, such as the London planes, black walnuts and newly planted trees. Trees under 6-inches in diameter can be physically relocated and other trees can be protected by implementing tree protection measures during the construction process.

#### **Construction Considerations**

A preliminary assessment of issues that will occur during construction are as follows:

- On-road bike traffic to be prohibited (provide signs to use multi-use path)
- One lane traffic to be used during non-peak hours
- Trees to be removed to grade and stumps/roots grinded below proposed subgrade to avoid disturbance of utilities or damage to existing roadbed
- Temporary easement is needed for construction equipment

It is estimated that construction will take 2 months.

#### **Environmental Overview**

The following is a summary of environmental studies on the project:

- No jurisdictional waters were identified in the study area.
- The study area contains habitat for the Indiana Bat. Impacts will require mitigation per coordination with the USFWS once final design and impacts have been established. Mitigation for tree clearing will be required no matter what time of year and a higher ratio will be required. Note: the report says ": "Tree clearing will not be allowed between June 1 and July 31".
- Five areas of habitat for running buffalo clover were found north of the Indian Hills Trail terminus, so this should not be a factor.
- Phase I HAZMAT has been conducted and revealed 2 gas stations and the LWC pumping facility; nothing that will be a factor in construction.
- Coordinate with DOW for permitting requirements: General Construction Permit and Floodplain
   Permit
- SHPO package is complete sent to Mike Jones (12/1/2011) then confirm and send package to SHPO for No Effects Determination.

 PM2.5 Checklist complete - Project Exempt – waiting to hear on who will handle IAC group confirmation.

#### **Cost Estimates**

The construction cost estimate for each alternative is as follows:

- 1. Widening to the north (left) = \$580,000
- 2. Widening to the south (right) = \$640,000
- 3. Symmetric Widening = \$600,000

Pavement Costs are based on 1.5 inches of asphalt surface; 7.5 inches of asphalt base and 8 inches of DGA. An existing pavement core should be taken before finalizing the pavement design for the project.

Appendix C shows the preliminary costs estimate breakdown for each alternative.

#### Recommendation

The alternative of widening to the north (left) is recommended because it avoids relocation of utility poles and water line; minimizes drainage/ditch work; affects only 5 parcels – 3 are park property – with Temporary Easements and has the lowest construction cost. Construction work should begin where the adjacent project ends, since that project is raising the grade of River Road at Zorn Avenue. Existing River Road should be restriped at Zorn Avenue for the new bike lanes. Other items with this alternative are:

- The Temporary Easement will be 15 feet off existing R/W line.
- The existing fence and single cable barrier will need to be removed and replaced (or rebuilt).
- Bollards on existing Multi-use path will need to be relocated
- Probable barrier (concrete or earth) between new bike lane and existing multi-use path between Stations 110+00 and 124+00.

The recommended multi-use path extension in the southeast corner between River Road and Indian Hills Trail at the end of the project is the flatter alignment that removes tree #177 (the center of the three Crabapple trees).

# APPENDIX A Comparison Matrix

#### RIVER ROAD ALIGNMENT STUDY

### SECTIONS:

ι	JTILITIES R	ELOCATIO	TREE CUTTING	TEMP. ESMNT.	NOTES	
FARM	GAS	WATER	UTILITY	#	R/W	
TAP	MAIN	MAIN	POLES	#	11,700	

#### Zorn Ave. to Mockingbird Road STA.100+00 TO STA.109+35

- Gas Station (NOT IMPACTED)
- Multi use on Left
- Farm Tap (Station 102+87 Left, RELOCATED BY OTHERS)
- Farm Tap (Station 105+93 Left, RELOCATED BY OTHERS)
- Wooden platform (Station 107+85 Right)
- Entrance to Lebanese-American Club Sign (Station 109+36 Right)
- Utilities impacted

Note: Improvements also part of KYTC project

Widening Left
Widening Right
Symmetric Widening

YES	NO	NO	YES	2	NO	
NO	NO	NO	YES	2	YES	
NO	NO	NO	YES	4	NO	

#### **Mockingbird Road to Turners Club Entrance**

#### STA.109+35 TO STA.114+41

- Multi use on Left
- Farm Tap (Station 112+84 Left)
- Stone Wall (Station 114+50 Right), oposite of Turners Club Entrance
- Utilities impacted
- Entrance (STA. 112+29, Right)

Widening Left
Widening Right
Symmetric Widening

YES	NO	NO	NO	10	NO	
NO	NO	YES	NO	2	NO	
NO	NO	NO	NO	0	NO	

#### **Turners Club Entrance to Waldoah Beach Road**

#### STA.114+41 TO STA.120+57

- Multi use on Left
- Stone Walls Left & Right (Station 120+57 Left) @ Waldoah Beach Entrance
- Utilities impacted

Widening Left
Widening Right
Symmetric Widening

NO	NO	NO	NO	13	NO	
NO	NO	YES	YES	WOODED AREA,NO #	YES	
NO	NO	YES	YES	5	NO	

#### RIVER ROAD ALIGNMENT STUDY

#### **SECTIONS:**

TILITIES R	ELOCATIO	TREE CUTTING	TEMP. ESMNT.	NOTES	
GAS	WATER	UTILITY	#	R/W	
		GAS WATER	GAS WATER UTILITY	GAS WATER UTILITY #	GAS WATER UTILITY # R/W

#### Waldoah Beach Road to Wagner Beach Road

#### STA.120+57 TO STA.124+36

- Multi use on Left
- Utilities impacted
- Storm Sewer Pipe (C.L. STA. 123+56)

Widening Left

Widening Right Symmetric Widening

Symmetric Widening

NO	YES	NO	NO	6	YES	
NO	NO	YES	YES	WOODED AREA,NO #	YES	
NO	NO	YES	YES	1	NO	

#### Wagner Beach Road to T.H. Park Entr. #1

#### STA.124+36 TO STA.126+34

- Multi use on Left
- Utilities impacted

Widening Left Widening Right Symmetric Widening

NO	YES	NO	NO	3	NO	
NO	NO	YES	YES	WOODED AREA,NO #	YES	
NO	NO	YES	YES	3	NO	

#### T.H. Park Entr. #1 to Cox Park Entr. #1

#### STA.126+34 TO STA.132+56

- Utilities impacted
- Wooden fence impacted,Left side
- Multi use on Left
- Multi use on Right

Widening Left Widening Right Symmetric Widening

NO	YES	NO	NO	11	NO	
NO	NO	NO	YES	14	YES	
NO	NO	NO	NO	18	NO	

#### Cox Park Entr. #1 to T.H. Park Entr. #2

#### STA.132+56 TO STA.147+11

- Utilities impacted
- Wooden fence impacted,Left side
- Wooden posts with single cable barrier impacted,Left side
- Multi use on Right
- Entrance Pipe (STA. 147+11, Right)

Widening Left
Widening Right
Symmetric Widening

NO	YES	NO	NO	15	NO	
NO	NO	NO	YES	24	YES	
NO	NO	NO	NO	13	NO	

#### RIVER ROAD ALIGNMENT STUDY

#### **SECTIONS:**

ι	JTILITIES R	ELOCATIO	TREE CUTTING	TEMP. ESMNT.	NOTES	
FARM TAP	GAS MAIN	WATER MAIN	UTILITY POLES	#	R/W	

#### T.H. Park Entr. #2 to Cox Park Entr. #2

#### STA.147+11 TO STA.151+33

- Utilities impacted
- Multi use on Right
- Police Station
- Storm Sewer Pipe with deep ditch rt. (C.L. STA. 148+05)

Widening Left
Widening Right
Symmetric Widening

NO	YES	NO	NO	7	NO	
NO	NO	NO	YES	11	NO	
NO	NO	NO	YES	8	NO	

#### Cox Park Entr. #2 to Golf Centers

#### STA.151+33 TO STA.159+44

- Utilities impacted
- Multi use on Right
- Entrance Pipe (STA. 151+33,Right)

Widening Left
Widening Right
Symmetric Widening

NO	NO	NO	NO	12	NO	
NO	NO	YES	YES	11	NO	
NO	NO	NO	YES	5	NO	

#### **Golf Centers to Indian Hills Trail**

#### STA.159+44 TO STA.165+63

- Patriot Peace Memorial Sign impacted (STA. 162+34, Right)
- Multi use on Right
- Utilities impacted
- Storm Sewer Pipe (C.L. STA. 164+73)

Widening Left Widening Right Symmetric Widening

NO	YES	NO	NO	8	NO	
NO	NO	YES	YES	13	YES	
NO	NO	NO	YES	15	NO	

Widening Left
Widening Right
Symmetric Widening

SUMMARY							
NO	YES	NUMBER <b>TEMP.</b>					
		OF TREES	ESMNT.				
31	9	87	YES				
18	22	77	YES				
30	10	72	NO				

# APPENDIX B Photo Log

### RIVER ROAD ALIGNMENT STUDY PHOTO LOG

Zorn Avenue to Mockingbird Road Sta. 100+00 to Sta. 109+35









Mockingbird road to Turners Club Entrance Sta. 109+35 to Sta. 114+41





Turners Club entrance to Waldoah Beach Road Sta. 114+41 to Sta. 120+57







Waldoah Beach Road to Wagner Beach Road Sta. 120+57 to Sta. 1234+36



Wagner Beach Road to T.H. Park Entr. #1 Sta. 124+36 to Sta. 126+34



T.H. Park Entr. #1 to Cox park Entr. #1 Sta. 126+34 to Sta. 132+56





Cox Park Entr. #1 to T.H. park Entr. #2 Sta. 132+56 to Sta. 147+11



T.H. Park Entr. #2 to Cox Park Entr. #2 Sta. 147+11 to Sta. 151+33



Cox Park Entr. #2 to Golf Centers Sta. 151+33 to Sta. 159+44





Golf Centers to Indian Hills Trail Sta. 159+44 to Sta. 165+63

#### Multi use to match



## APPENDIX C Cost Estimates

#### LOUISVILLE METRO

#### **Bureau of Highways**

## PRELIMINARY ESTIMATE OF CONSTRUCTION COSTS Addition 8' of Pavement for Bike Lanes\_Left Side, Overlay & Drainage Improvements

County: **JEFFERSON** Item No: **0-000.00** 

UPN

To:

Road Name: From:

RIVER ROAD STA. 100+00 STA: 167+89.59

Net Length, mile: 1.29 Type of Construction: Grade & Drain & Surfacing Class of Road: Rural Arterial

Item #	Item	Quantity	Unit	Unit Price	Amount	
2200	Roadway Excavation	2,276	CU YD	\$15.00	34,140	
0001	C.S.B. or DGA	3,935	TON	\$20.00	78,700	
0212	Asph Base	2,000	TON	\$65.00	130,000	
0301	Asph Surf	1,954	TON	\$75.00	146,550	
0291	Emulsified Asphalt	3	TON	\$650.00	1,950	
0100	Asphalt Seal Aggregate	29	TON	\$65.00	1,885	
	Leveling and Wedging	65	TON	\$75.00	4,875	
0520	12" Storm Sewer Pipe	5	LIN FT	\$45.00	225	
0522	18" Storm Sewer Pipe	10	LIN FT	\$45.00	450	
1517	DBI Type 5F	1	EACH	\$1,600.00	1,600	
2723	Sidewalk 6" Concrete	111	SQ YD	\$31.00	3,441	
	Maintain and Control Traffic	1	LP SUM	\$50,000.00	50,000	
	Clearing and Grubbing	1	LP SUM	\$15,000.00	15,000	
	Staking	1	LP SUM	\$6,000.00	6,000	
	+ 5% for items not estimated				23,741	
					·	
	SUB-TOTAL GRADE, DRAIN, AND SURFACING:				498,557	
	Mobilization (@3%)					
	Demobilizaton (@ 1-1/2%)				7,478	
	SUB-TOTAL					
			+15%	Engr. & Contg.	<b>506,035</b> 75,905	
GRAND-TOTAL				581,940		

Estimated by: Z. Ajanovic Date: 11-29-2011 Checked by: Date: 11-29-2011

1 Cut = 2,276, Fill = 1,668

#### LOUISVILLE METRO

#### **Bureau of Highways**

## PRELIMINARY ESTIMATE OF CONSTRUCTION COSTS Addition 8' of Pavement for Bike Lanes\_Right Side, Overlay & Drainage Improvements

County: **JEFFERSON** Item No: **0-000.00** 

UPN

To:

Road Name: From:

RIVER ROAD STA. 100+00 STA: 167+89.59

Net Length, mile: 1.29 Type of Construction: Grade & Drain & Surfacing Class of Road: Rural Arterial

Item #	Item	Quantity	Unit	Unit Price	Amount
2200	Roadway Excavation	3,007	CU YD	\$15.00	45,105
0001	C.S.B. or DGA	3,935	TON	\$20.00	78,700
0212	Asph Base	2,000	TON	\$65.00	130,000
0301	Asph Surf	1,954	TON	\$75.00	146,550
0291	Emulsified Asphalt	3	TON	\$650.00	1,950
0100	Asphalt Seal Aggregate	29	TON	\$65.00	1,885
	Leveling and Wedging	65	TON	\$75.00	4,875
0520	15" Storm Sewer Pipe	90	LIN FT	\$45.00	4,050
0522	18" Storm Sewer Pipe	70	LIN FT	\$45.00	3,150
1641	Junction Box 18"	13	EACH	\$1,883.00	24,479
0736	Metal End Section TY 3-18 Inch	4	EACH	\$1,114.00	4,456
1517	DBI Type 5F	2	EACH	\$1,600.00	3,200
2723	Sidewalk 6" Concrete	111	SQ YD	\$31.00	3,441
					·
	Maintain and Control Traffic	1	LP SUM	\$50,000.00	50,000
	Clearing and Grubbing	1	LP SUM	\$15,000.00	15,000
	Staking	1	LP SUM	\$6,000.00	6,000
	+ 5% for items not estimated	•	21 00111	ψο,σσσ.σσ	26,142
	1 676 for Romo not Colimated				20,142
			†		
	SUB-TOTAL GRADE, DRAIN, AND SURFACING:			+	548,983
	Mobilization (@3%)				
	Demobilization (@ 1-1/2%)		1		8,235
	2022		1		5,200
		SUB-TOTAL	557,218		
	+15% Engr. & Contg.				83,583
			SRAND-TOTAL	640,801	

Estimated by: Z. Ajanovic Date: 11-29-2011 Checked by: Date: 11-29-2011

1) Cut = 3,007, Fill = 1,605

#### LOUISVILLE METRO

#### **Bureau of Highways**

## PRELIMINARY ESTIMATE OF CONSTRUCTION COSTS Addition 8' of Pavement for Bike Lanes\_ Left & Right Side, Overlay & Drainage Improvements

County: **JEFFERSON** Item No: **0-000.00** 

UPN Road Name:

From:

RIVER ROAD STA. 100+00 STA: 167+89.59

To: STA: 167+89.59

Net Length, mile: 1.29 Type of Construction: Grade & Drain & Surfacing Class of Road: Rural Arterial

Item #	Item	Quantity	Unit	Unit Price	Amount
2200	Roadway Excavation	3,680	CU YD	\$15.00	55,200
0001	C.S.B. or DGA	3,791	TON	\$20.00	75,820
0212	Asph Base	1,800	TON	\$65.00	117,000
0301	Asph Surf	1,917	TON	\$75.00	143,775
0291	Emulsified Asphalt	7	TON	\$650.00	4,550
0100	Asphalt Seal Aggregate	57	TON	\$65.00	3,705
	Leveling and Wedging		TON	\$75.00	(
0522	18" Storm Sewer Pipe	70	LIN FT	\$45.00	3,150
1641	Junction Box 18"	4	EACH	\$1,883.00	7,53
0736	Metal End Section TY 3-18 Inch	4	EACH	\$1,114.00	4,45
1517	DBI Type 5F	1	EACH	\$1,600.00	1,600
2723	Sidewalk 6" Concrete	111	SQ YD	\$31.00	3,44
	Old Wall Control of the Control of t		04.2	, ,	0,
	_				
	1				
	_				
	+				
	Maintain and Control Traffic	1	LP SUM	\$50,000.00	50,00
	Clearing and Grubbing	1	LP SUM	\$15,000.00	15,00
	Staking	1	LP SUM	\$6,000.00	6,00
	+ 5% for items not estimated				24,56
	SUB-TOTAL GRADE, DRAIN, AND SURFACING:				515,79
	Mobilization (@3%)				
	Demobilizaton (@ 1-1/2%)				7,73
		SUB-TOTAL			
			+15%	Engr. & Contg.	<b>523,52</b> 78,52
				GRAND-TOTAL	602,05

Estimated by: Z. Ajanovic Date: 11-29-2011 Checked by: Date: 11-29-2011

1) Cut = 3,680, Fill = 1,287

